


Thomas Armstrong (Construction) Limited



CLIENT: Washington Estates

PROJECT: Extension to Drigg Grout Facility

VALUE: £400,000

COMPLETION: September 2004

CONTRACT: GC Works 1

DURATION: 24 weeks

PROJECT DESCRIPTION:

The works contracted at the extension of the Grouting Facility compound at Drigg comprised of the demolition of existing concrete perimeter wall to three sides of the yard, removal of existing paving's and concrete planning works to the existing areas for the new specification construction. Excavation and new base construction to extend the block paved yard area. New 3m high reinforced concrete perimeter wall to the extended yard area. New external lighting and misc. items.

The specification for the new paving was to a very precise specification previously specified on airport runways to take extreme loading. All materials used undertook rigorous testing to ensure that they met with the very detailed contract specification.

The project was also carried out around the continuing operations of the grout facility.

