


# Thomas Armstrong (Construction) Limited



**CLIENT:** Lakes Homecentre, Cockermouth

**PROJECT:** Installation of Mezzanine Floor

**COMPLETION:** March 2010

**CONTRACT:** JCT D&B

## **PROJECT DESCRIPTION:**

A challenging contract with respect to the contract period, client requirement to continue trading and maintaining shop frontage access throughout the contract period.

A birdcage scaffold was required and hoarded off segregation for the installation for the works.

A structural steelwork frame was installed for the new mezzanine, joisted and decked out, formation of a new fire escape enclosure, disabled and goods lifts were installed and the existing sales area/warehouse wall upgraded to 1 hour fire resistance. Extensive electrical works were involved to the power and lighting circuits as



well as the introduction of an Air Conditioning System.

Early fit out was achieved, allowing the client to log floor finishes, erect shelving and re-merchandise prior to opening for Easter.

